



BATAAN GENERAL HOSPITAL
Balanga City, Bataan



**BILL OF MATERIALS AND LABOR FOR THE
CONSTRUCTION OF FIVE (5) STOREY MULTI-SPECIALTY BUILDING (PHASE II)**

I MASONRY WORKS

5" x 8" x 16" CHB	pc	88,408		
Washed Sand	m ³	651		
Portland Cement	bag	9,520		
10mmØ x 6m RSB	kg.	19,314		
#16 GI Tie Wire	kg.	298		
			Material Cost	Php _____
			Labor Cost	_____
			Total Cost of Item	Php _____

II FORMS & SCAFFOLDINGS

H-Frame Scaffoldings (rental)	set	440		
			Material Cost	Php _____
			Labor Cost	_____
			Total Cost of Item	Php _____

III ROOF FRAMING WORKS

Top Chord, Bottom Chord, Web Members				
¼" x 2 1/2" x 2 1/2" x 6m Angle Bar	pc.	248		Php _____
¼" x 2" x 2" x 6m Angle Bar	pc.	219		
Purlins & Fascia Board Connector				
¼" x 2" x 2" x 6m Angle Bar	pc.	3		
Base Plate & Anchor Bolts				
1/2" x 4' x 8' M.S. Plate	pc.	2		
¼" x 4' x 8' M.S. Plate	pc.	16		
16mmØ x 14" Anchor Bolt	pc.	456		
Purlins				
2"x 6"x 2.0mm C-Purlins	pc.	157		
Sag Rod and Cross Bracing				
16mmØ Sag Rod	pc.	268		
16mmØ Cross Bracing	pc.	68		
Welding Rod	box	4		
Epoxy Paint w/ Catalyst	gal.	22		
Oxygen/Acetylene, Cutting Outfit, G. Disc, H. Blade Etc.	l.s			
			Material Cost	Php _____
			Labor Cost	_____
			Total Cost of Item	Php _____

IV ROOFING & TINSMITHRY WORKS

Long Span Coloroof Rib Type Roofing Shts (.5mm thick)	l.m.	859		Php _____
#24 Prepainted Ridge Cap	pc.	21		
#24 Prepainted Gutter	pc.	45		
#24 Prepainted Flashing	pc.	29		
12mm Roof Insulation	m ²	732		
2½ Tek screw	pc.	3,818		
Blind Rivets	box	5		
Roof Sealant	lit.	10		
			Material Cost	Php _____
			Labor Cost	_____
			Total Cost of Item	Php _____

V CARPENTRY WORKS

60cm x 60cm Acoustical Board on Alum. T. Runner	m ²	4,041		
1/4 " x 4' x 8' Fiber Cement Board	pc.	164		
3/4" x 4' x 8' Phenolic Board	pc.	52		
Furring Channel	pc.	249		
Carrying Channel	pc.	188		
Wall Angle	pc.	252		
#16 G.I. Tie Wire	kg.	20		
Suspension Clip	pc.	1,314		
Wire Clip	pc.	1,972		
Screw	pc.	4,427		
2 1/2' x 5' x 1/4" Mirror	pc.	8		
2 1/2' x 4' x 1/4" Mirror	pc.	2		

Stage Flooring
Aluminum Cabinets (under counter top/ sink)

m² 37
lot

Material Cost	Php	<div></div>
Labor Cost		
Total Cost of Item	Php	<div></div>

VI	DOORS & WINDOWS				
	All Doors with Complete Accessories : LOCKSET & ALL REQUIRED				
	DOOR CLOSER & DOOR STOPPER WITH METAL JAMB				
	4.0m X 2.40m Double Leaf, Double -Swing Door with 6mm thk Clear Glass on Aluminum				
D1-	Powder Coated Frame	set	1		Php
	2.0m X 2.40m Double Leaf, Double -Swing Door with 6mm thk Clear Glass on Aluminum				
D2-	Powder Coated Frame	set	7		
D3-	2.0m X 2.40m Double Leaf, Double -Swing Flush Door	set	1		
	1.80m X 2.40m Double Leaf, Double -Swing Door with 6mm thk Clear Glass on Aluminum				
D4-	Powder Coated Frame	set	3		
	1.60m X 2.40m Double Leaf, Double -Swing Door with 6mm thk Clear Glass on Aluminum				
D5-	Powder Coated Frame	set	4		
	1.60m X 2.40m Double Leaf, Double -Swing Flush Door W/ 6mm thk viewing glass and kick plate				
D6-		set	8		
D8-	1.10m X 2.40m Single -Swing Flush Door w/ 6mm thk viewing glass and kick plate	set	1		
D9-	1.0m X 2.40m Single -Swing Flush Door w/ kick plate	set	97		
D10-	1.0m X 2.40m Single -Swing galvanized steel door w/ 6mm thk fixed clear glass	set	11		
D11-	0.80m X 2.10m Single -Swing flush door	set	29		
D12-	0.70m X 2.10m Single -Swing flush door	set	44		
D13-	1.0m X 2.10m Sliding flush door	set	1		
W3-	2.0m X 2.10m Aluminum Powder Coated Awning and Fixed Window with insect screen ands grills	set	9		
W4-	2.0m X 1.50m Aluminum Powder Coated Awning and Fixed Window with insect screen ands grills	set	155		
W5-	2.0m X 0.90m Aluminum Powder Coated Awning Window with insect screen ands grills	set	32		
W7-	1.0m X 0.90m Aluminum Powder Coated Awning Window with insect screen ands grills	set	2		
W8-	1.0m X 1.50m Aluminum Powder Coated Awning and Fixed Window with insect screen ands grills	set	12		
W9-	0.60m X 0.90m Aluminum Powder Coated Awning Window with insect screen ands grills	set	12		
				Material Cost	
				Installation Cost	
				Total Cost of Item	Php
VII	TILE WORKS				
	60" X 60" Homogenous Floor Tiles	pc.	10,922		Php
	60" X 60" Non Skid Homogenous Floor Tiles	pc.	1,880		
	60" X 60" Homogenous Wall Tiles	pc.	1,170		
	60" X 60" Homogenous Splash Wall Tiles	pc.	212		
	60" X 60" Vinyl Tiles	pc.	434		
	40" X 40" Ceramic Floor Tiles	pc.	669		
	40" X 40" Homogenous Wall Tiles	pc.	2,696		
	Anti-bacterial Vinyl Flooring	m ²	96		
	Tile Trim 10'	pc.	114		
	Washed Sand	m ³	94		
	Portland Cement	bag	1,336		
	Vinyl Tile Adhesive	gal	13		
	Tile Grout	bag	161		
	Brass Stair Nosing (1.3m)	pc.	331		
	Brass Stair Nosing (2.6m)	pc.	3		
	Brass Stair Nosing (5.6m)	pc.	3		
	Cutting Disc	pc.	30		
				Material Cost	Php
				Labor Cost	
				Total Cost of Item	Php
VIII	WATERPROOFING				
	Toilet	m ²	196		Php
	Roof deck	m ²	234		
	Elevator Pit	m ²	97		
				Material Cost	Php
				Labor Cost	
				Total Cost of Item	Php
IX	METAL WORKS				
	1 1/2"Ø Stainless Pipe	pc.	83		Php
	Aluminum Wall Panel	m ²	243		
	2" x 4" x 1.2mm Tubular Bar	pc.	39		
	Welding Rod	box	1		
				Material Cost	
				Labor Cost	
				Total Cost of Item	Php
X	SANITARY & PLUMBING WORKS				
	A. Fixtures				
	Water Closet, elongated, tank type, dual flush valve	set	66		Php
	Waterless Toilet bowl	set	1		
	Urinal Bowl	set	9		
	Lavatory	set	63		
	Stainless Sink	set	43		

Wall Faucet	pc.	42		
Foot Operated Faucet	pc.	3		
Floor Drain	pc.	87		
Deck Drain	pc.	11		
Shower Head & Valve, (wall mounted mixing valve)	pc.	11		
			Sub-total	Php <hr/>

B. ACU and Storm Drainage System

400mmØ PVC Pipe (Downspout)	pc.	14		
200mmØ PVC Pipe (Downspout)	pc.	45		
100mmØ PVC Pipe (VSTR)	pc.	12		
50mmØ PVC Pipe (VP)	pc.	345		
25mmØ PVC Pipe	pc.	375		
200mmØ PVC Elbow	pc.	50		
200mmØ PVC Tee	pc.	47		
25mmØ PVC Elbow	pc.	288		
25mmØ PVC Tee	pc.	85		
400mmØ RC Pipe	l.m.	46		
Teflon Tape	roll	100		
PVC Solvent cement	lit.	10		
Other Materials & Fittings	l.s.			
			Sub-total	Php <hr/>

C. Water Pumps and Tanks

Stainless Steel Tank 2000 gals (6mm thick)	unit	2		
Bladder tank	unit	1		
Elevated Water Tank	unit	1		
Water pump (3 HP, 230V)	unit	3		
Submersible Pump (1.5 HP, 60GPM, 60ft. TDH, 3500 RPM, 60 Hz)	unit	1		
			Material Cost	Php <hr/>
			Installation Cost	

Equipment Cost (Pumps and Tanks)	Php
Material Cost	
Labor/ Installation Cost	
Total Cost of Item	Php <hr/>

XI ELECTRICAL WORKS

A. Panel Board & Circuit Breakers

Powerhouse MDP Panel Box, 3-Phase, 6 Holes (NEMA-1 Standard GA.# 16, Encl., Gray Powder Coated Finish)	unit	1
MDP Panel Box, 3-Phase, 10 Holes (NEMA-1 Standard GA.# 16, Encl., Gray Powder Coated Finish)	unit	1
MLPP Panel Box, 3-Phase, 6 Holes (NEMA-1 Standard GA.# 16, Encl., Gray Powder Coated Finish)	unit	3
MLPP Panel Box, 3-Phase, 4 Holes (NEMA-1 Standard GA.# 16, Encl., Gray Powder Coated Finish)	unit	3
Elevator Electrical Panel Box, 3-Phase, 8 Holes (NEMA-1 Standard GA.# 16, Encl., Gray Powder Coated Finish)	unit	2
Industrial Panel Box, 3-Phase, 6 Holes (NEMA-1 Standard GA.# 16, Encl., Gray Powder Coated Finish)	unit	1
Panel Box, 3-Phase, 20 Holes (NEMA-1 Standard GA.# 16, Encl., Gray Powder Coated Finish)	unit	4
Panel Box, 3-Phase, 18 Holes (NEMA-1 Standard GA.# 16, Encl., Gray Powder Coated Finish)	unit	1
Panel Box, 3-Phase, 16 Holes (NEMA-1 Standard GA.# 16, Encl., Gray Powder Coated Finish)	unit	2
Panel Box, 3-Phase, 14 Holes (NEMA-1 Standard GA.# 16, Encl., Gray Powder Coated Finish)	unit	3
Panel Box, 3-Phase, 12 Holes (NEMA-1 Standard GA.# 16, Encl., Gray Powder Coated Finish)	unit	2
Panel Box, 3-Phase, 6 Holes (NEMA-1 Standard GA.# 16, Encl., Gray Powder Coated Finish)	unit	1
Panel Box, 3-Phase, 4 Holes (NEMA-1 Standard GA.# 16, Encl., Gray Powder Coated Finish)	unit	1

Molded Case Circuit Breaker 3200AT/3200AF, 3-Phase, 220-240V, w/ 6 Cable Lugs per Phase, w/ (NEMA-1 Standard GA.# 16, Encl., Gray Powder Coated Finish)	unit	3		
Molded Case Circuit Breaker 150AT/225AF, 3-Phase, 220-240V & Motor Controller w/ (NEMA-1 Standard GA.# 16, Encl., Gray Powder Coated Finish)	unit	2		
Molded Case Circuit Breaker 30AT/100AF, 3-Phase, 220-240V & Motor Controller w/ (NEMA-1 Standard GA.# 16, Encl., Gray Powder Coated Finish)	unit	2		
Molded Case Circuit Breaker 3200AT/3200AF, 3-Phase, 220-240V, w/ 6 Cable Lugs per Phase	pc.	1		
Molded Case Circuit Breaker 1600AT/1600AF, 3-Phase, 220-240V, w/ 4 Cable Lugs per Phase	pc.	2		
Molded Case Circuit Breaker 400AT/400AF, 3-Phase, 220-240V	pc.	6		
Molded Case Circuit Breaker 250AT/400AF, 3-Phase, 220-240V	pc.	10		
Molded Case Circuit Breaker 200AT/225AF, 3-Phase, 220-240V	pc.	2		
Molded Case Circuit Breaker 150AT/225AF, 3-Phase, 220-240V	pc.	8		
Molded Case Circuit Breaker 125AT/225AF, 3-Phase, 220-240V	pc.	2		
Molded Case Circuit Breaker 110AT/225AF, 3-Phase, 220-240V	pc.	8		
Molded Case Circuit Breaker 100AT/225AF, 3-Phase, 220-240V	pc.	2		
Molded Case Circuit Breaker 100AT/100AF, 3-Phase, 220-240V	pc.	6		
Molded Case Circuit Breaker 90AT/100AF, 3-Phase, 220-240V	pc.	5		
Molded Case Circuit Breaker 80AT/100AF, 3-Phase, 220-240V	pc.	4		
Molded Case Circuit Breaker 50AT/100AF, 3-Phase, 220-240V	pc.	2		
Molded Case Circuit Breaker 30AT/100AF, 3-Phase, 220-240V	pc.	2		
30AT/100AF Circuit Breaker, 220-240V	pc.	128		
20AT/100AF Circuit Breaker, 220-240V	pc.	79		
20AT/50AF Circuit Breaker, 220-240V	pc.	6		
			Sub-total	Php

B. Lighting and Other Fixtures

Reccesed Type, Lighting Fixture w/ 15W LED w/ cover	set	422		
Troffer Lighting Fixture w/ 20W Led w/ cover	set	142		
20W LED Fluorescent Lamp w/ cover	set	24		
Focus Light w/ 15W LED	set	7		
LED Exit Light	unit	10		
LED Emergency Light, 2 x 10W	unit	89		
1 Gang Switch 10Amp. Rating w/ plate cover	set	86		
2 Gang Switch 10Amp. Rating w/ plate cover	set	100		
3 Gang Switch 10Amp. Rating w/ plate cover	set	14		
3 Way Switch 10Amp. Rating w/ plate cover	set	28		
Convenience Outlet (Single w/ Ground) 15Amp. Rating	set	102		
Convenience Outlet (Duplex w/ Ground) 15Amp. Rating	set	412		
Convenience Outlet (Duplex w/ Ground) 15Amp. Rating (Floor Outlet)	set	20		
Aircon Outlet	set	3		
			Sub-total	Php

C. Wires, Cables and Other Materials

Junction Box w/ cover	pc.	1355		
Utility Box	pc.	765		
PVC Elec. Pipe 20mm dia.	pc.	4577		
PVC Elec. Pipe 25mm dia.	pc.	1483		
PVC Elec. Pipe 40mm dia.	pc.	30		
PVC Elec. Pipe 50mm dia.	pc.	3		
PVC Elec. Pipe 32mm dia.	pc.	3		
PVC Elec. Pipe 65mm dia.	pc.	37		
PVC Elec. Pipe 80mm dia.	pc.	38		
PVC Elec. Pipe 100mm dia.	pc.	8		
Conduit Fittings	lot	1		
Stranded Wire 5.5mm ² THHN	l.m.	8,900		
Stranded Wire 3.5mm ² THHN	l.m.	36,998		
Stranded Wire 30mm ² THHN	l.m.	162		
Stranded Wire 38mm ² THHN	l.m.	27		
Stranded Wire 8.0mm ² THHN	l.m.	27		
Stranded Wire 22mm ² THHN	l.m.	150		
Stranded Wire 50mm ² THHN	l.m.	270		
Stranded Wire 125mm ² THWN/THHN-2	l.m.	342		
Stranded Wire 80mm ² THWN/THHN-2	l.m.	63		
Stranded Wire 250mm ² THWN/THHN-2	l.m.	72		
Stranded Wire 400mm ² THWN/THHN-2	l.m.	1000		
Stranded Wire 14mm ² TW	l.m.	129		
Stranded Wire 5.5mm ² TW	l.m.	9		
Stranded Wire 8.0mm ² TW	l.m.	81		
Stranded Wire 22mm ² TW	l.m.	114		
Stranded Wire 30mm ² TW	l.m.	24		

	100 mm dia. RSC	pc.	12			
	100 mm dia. Coupling RSC	pc.	12			
	100 mm dia. Conduit Elbow RSC	pc.	12			
	100 mm dia. Service Entrance Cap RSC	pc.	12			
	100 mm dia. Male Adaptor RSC	pc.	12			
	Cabling Tray	lot	1			
				Sub-total	Php	
	D. Lightning Protection and Grounding System					
	Lightning Protection System (Early Streamer Emmission) w/ Aircraft	lot	1			
	Obstruction Light Fixtures					
	Grounding Rod, 20mmØ x 3 meters, Copper Clad Steel	pc.	43			
	PVC Elec. Pipe 32mmØ	pc.	67			
	Conduit Fittings	lot	1			
	100mm ² Bare Copper Wire	l.m.	200			
				Sub-total	Php	
	E. Power/ Generator House	m ²	72			
				Sub-total	Php	
	F. Generator, ATS, Transformer					
	333KVA Distribution Transformer	unit	3			
	Accessories & Fittings (for 333KVA Distribution Transformer)	lot	1			
	1000KVA Generator Set, 3-phase, Silent Type, 220V-240V, Manual &	unit	2			
	Automatic, w/ 6 Cable Lugs per Phase					
	Automatic Transfer Switch (ATS) 3200 Ampere, 3-phase, 220V-240V, w/ 6	unit	1			
	Cable Lugs per Phase					
	Manual Transfer Switch (MTS) 3200 Ampere, 3-phase, 220V-240V, w/ 6	unit	1			
	Cable Lugs per Phase					
				Sub-total	Php	
				Installation Cost		
				Equipment Cost (Generator, ATS, Transformer)	Php	
				Material Cost		
				Labor/ Installation Cost		
				Total Cost of Item	Php	
XII	MECHANICAL WORKS					
	A. Fire Protection System					
	-Fire Alarm System					
	12 Zone Fire Alarm Control Panel	set	1			
	Fire Alarm Manual Station	set	12			
	Conventional Smoke Detector	set	114			
	Conventional Heat Detector	set	1			
	Fire Alarm Box	set	4			
	Fire Alarm Bell	set	12			
	Annunciator	set	5			
	Junction Box	pc.	114			
	Utility Box	pc.	114			
	PVC Elec. Pipe 20mmØ	pc.	1,245			
	Conduit Fittings	lot	1			
	1.25mm ² , TF Wire	l.m.	7,468			
				Sub-total	Php	
	-Sprinkler System					
	Pipes and Fittings					
	150mmØ B.I. Pipe Sch. 40	pc.	22			
	100mmØ B.I. Pipe Sch. 40	pc.	43			
	75mmØ B.I. Pipe Sch. 40	pc.	55			
	40mmØ B.I. Pipe Sch. 40	pc.	10			
	32mmØ B.I. Pipe Sch. 40	pc.	41			
	25mmØ B.I. Pipe Sch. 40	pc.	238			
	100mmØ B.I. Tee Sch. 40	pc.	11			
	32mmØ B.I. Tee Sch. 40	pc.	108			
	25mmØ B.I. Tee Sch. 40	pc.	230			
	150mmØ x 100mmØ B.I. Tee Reducer Sch. 40	pc.	8			
	150mmØ x 65mmØ B.I. Tee Reducer Sch. 40	pc.	1			
	100mmØ x 65mmØ B.I. Tee Reducer Sch. 40	pc.	1			
	100mmØ x 40mmØ B.I. Tee Reducer Sch. 40	pc.	5			
	100mmØ x 32mmØ B.I. Tee Reducer Sch. 40	pc.	5			
	75mmØ x 40mmØ B.I. Tee Reducer Sch. 40	pc.	12			

75mmØ x 32mmØ B.I. Tee Reducer Sch. 40	pc.	107		
100mmØ x 75mmØ B.I. Coupling Reducer Sch. 40	pc.	5		
32mmØ x 25mmØ B.I. Coupling Reducer Sch. 40	pc.	216		
150mmØ B.I. Elbow 90° Sch. 40	pc.	2		
100mmØ B.I. Elbow 90° Sch. 40	pc.	20		
40mmØ B.I. Elbow 90° Sch. 40	pc.	45		
32mmØ B.I. Elbow 90° Sch. 40	pc.	6		
25mmØ B.I. Elbow 90° Sch. 40	pc.	255		
150mmØ B.I. End Cap Sch. 40	pc.	1		
100mmØ B.I. End Cap Sch. 40	pc.	1		
75mmØ B.I. End Cap Sch. 40	pc.	5		
50mmØ B.I. End Cap Sch. 40	pc.	1		
Flexible Coupling 150mmØ	pc.	20		
Flexible Coupling 100mmØ	pc.	20		
Flexible Coupling 75mmØ	pc.	40		
<i>Sprinkler Heads, Valves, Connections and other accessories</i>				
OS & Y Gate Valve 100mmØ	pc.	5		
OS & Y Gate Valve 150mmØ	pc.	2		
Fire Hose Valve 65mmØ	pc.	13		
Alarm Check Valve w/ Gong 150mmØ	set	1		
Fire Hose Cabinet Recessed Type with complete accessories	set	15		
Fire Dept. Connection (2-way) Dry Type	set	1		
Fire Dept. Connection (2-way) Wet Type	set	1		
Sight Glass 25mmØ	pc.	5		
Globe Valve 25mmØ	pc.	5		
Sprinkler Heads (QRS Pendent Type with Ceiling Plate) UL Listed	pc.	545		
Fire Extinguishers 10 lbs, ABC type, Dry Chemical	pc.	15		
Flow Switch 100mmØ	pc.	7		
Sprinkler Alarm Control Panel	set	1		
<i>Hangers and Supports</i>				
Clevis Hanger 100mmØ	pc.	25		
Clevis Hanger 75mmØ	pc.	95		
Loop Hanger 25mmØ	pc.	474		
<i>Other Materials</i>				
200mmØ PVC Pipe	pc.	5		
150mmØ PVC Pipe	pc.	6		
50mmØ PVC Pipe	pc.	35		
Juction box w/ cover	pc.	5		
PVC Elec. Pipe 20mmØ	pc.	23		
1.5mm²,TF Wire	l.m.	275		
Teflon Tape 3/4"	pc.	500		
U-bolt 1/4" x 6" with Nut and Washer	pc.	50		
U-bolt 1/4" X 4" with Nut and Washer	pc.	50		
Angle Bar 1 1/2" x 1 1/2" x 1/8" thk	pc.	50		
Hexagonal Nut 3/8"	pc.	650		
Threaded Rod (Continous) 3/8"	pc.	250		
Expansion Shield 3/8"	pc.	650		
			Sub-total	Php <hr/>
-Water Tank and Pump House				
Domestic and Firewater Reservoir	m³	178		
Pump House	m²	12		
			Sub-total	Php <hr/>
-Pumps and Controllers				
Fire Pump (Vertical Turbine)				
-Vertical Turbine Pump shall be complete with discharge head assembly, air release, pressure gauge, coupled to an electric motor with WPI enclosure 445TP frame & other standard accesories.				
- 500 gpm, 3650 rpm, 50 HP, 230 V, 3 PH, 60 Hz	set	1		
Fire Pump Controller				
- Fire Pump controller shall be wye delta reduced voltage starting open during transition from start to run, controllers shall be floor mounted on NEMA type 4 enclosure to include pump operating pilot lights, pump fail to start, pump over-load, alarm, test timer solenoid valve, UL/FM approved.				
- 230 V, 3 PH, 60 Hz				
Jockey Pump (Submersible Pump)				
- Submersible Centrifugal Pump, electric driven motor, complete with standard accessories, UL/FM approved, Jockey pump shall be connected load to the emergency generator, enclosure shall be as per manufacturer's recommendation.				
- 50 gpm, 3650 rpm, 5 HP, 230 V, 3 Ph, 60 Hz	set	1		

Jockey Pump Controller									
- Jockey Pump controller shall include the circuit breaker, over load relay, pressure switch, running period timer, all NEMA type enclosure, pressure recorder, power on pilot lights and other accessories, UL/FM approved.									
- 230 V, 3 PH, 60 Hz									
								Sub-total	Php
								Installation Cost	
B. Ventilation and Air-Conditioning System									
3 TR Aircondition Unit (Inverter Type, 3-phase)	4	unit							
1HP Aircondition Unit (Split Type, Inverter Type)	37	unit							
1.5HP Aircondition Unit (Split Type, Inverter Type)	17	unit							
2HP Aircondition Unit (Split Type, Inverter Type)	35	unit							
2HP Aircondition Unit (Window Type, Inverter Type)	3	unit							
Ceiling Fan (Orbital)	26	unit							
Exhaust Fan, Ceiling Mounted	47	unit							
								Sub-total	Php
								Installation Cost	
								Equipment Cost (Pumps, Controllers, VAC System)	Php
								Material Cost	
								Labor Cost/ Installation Cost	
								Total Cost of Item	Php
XIII PAINTING WORKS									
Flat Latex Paint	tin	115							
Semi-gloss Latex Paint	tin	41							
Gloss Latex Paint	tin	187							
Anti-bacterial Latex Paint	tin	2							
Quick Drying Enamel	gal.	6							
Acry Color	lit.	57							
Masonry Putty	gal.	438							
Concrete Nuetralizer	gal.	39							
Paint Thinner	gal.	5							
Red Oxide Primer	gal.	3							
Roller Brush with tray	pc.	50							
Paint Brush 4"	pc.	75							
Paint Brush 2"	pc.	75							
Sand Paper	pc.	500							
								Material Cost	Php
								Labor Cost	
								Total Cost of Item	Php
XIV ELEVATOR SYSTEM									
A. Machine RoomLess Passenger Type Elevator				unit	2				
- 1000 kgs. capacity x 6 stops								Sub-total	Php
- 220V, 3 phase, 60 Hz									
- Gearless PM Motor									
- 1600mm (W) x 1700mm (L) x 2300mm (H)									
- Center Opening Door									
- Stainless Steel Finish									
- With Auto Rescue Device									
- With Voltage Surge Supressor									
*Including Installation Cost									
B. Dumbwaiter Table Type				unit	1				
- 100 kgs. capacity x 4 stops								Sub-total	Php
- 220V, 3 phase, 60 Hz									
- 60mm (W) x 60mm (L) x 80mm (H)									
- Stainless Steel Finish									
*Including Installation Cost									
								Total Cost of Item	Php
XV SIGNAGES & MARKINGS									
Stainless Build-Up Letter	lot	1							Php
Acrylic Plastic w/ Sticker	lot	1							

Directory Board		pc.	1	Total Cost of Item	Php <div></div>
XVI	MOBILIZATION/ DEMOBILIZATION	lot			Php